# **Spiral Waste Bin Syste** www.mahamekar.com

**Refuse Storage & Handling Solution** 

# THE SPIRAL WASTE BIN SYSTEM

## **Delivery & Installation of Spiral Waste Bin at Project Site**

Our Spiral Waste Bin & Bin Lifter Systems are fully fabricated and pre-tested in our factory prior to delivery to the project site.

Delivery of Spiral Waste Bin & Bin Lifter System to project site is by lorry and loading and unloading of Spiral Waste Bin & Bin Lifter System is using our own crane or forklift

Prior to Delivery of Spiral Waste Bin & Bin Lifter System to project site, our technicians will check with client's Project / Site Manager to ensure the following :

- Supply of electricity for installation & testing (415V, 3 Phase, 32A Isolator)
- Supply of water via tap points for installation and testing purposes
- · Clearing of bin centre from debris and building material
- Access road to the bin centre is clear for delivery lorry and crane
- Operational roller-shutter to ensure the security of the Spiral Waste Bin after installation



UNLOADING OF THE SPIRAL WASTE BIN SYSTEM AT PROJECT SITE





LOADING OF THE SPIRAL WASTE BIN SYSTEM AT OUR FACTORY



#### At the Project Site

#### Unloading & Positioning of the Spiral Waste BIn System

Upon unloading at project site, the Spiral Waste Bin & Bin Lifter System will be positioned at the optimal location in the refuse centre using rollers and manual labour.

#### Installation of the Spiral Waste BIn System

The Spiral Waste Bin & Bin Lifter System will be securely bolted to the floor at the designated position. Each leg of the Spiral Waste Bin System is bolted down with a 6" rawplug and the Bin Lifter System is bolted down with 8 nos. of 6" rawplug.

Connection from Isolator (3-Phase, 415V, 32 Amp) to Spiral Waste Bin Control Panel to is by 4mm copper wire c/w G.I. trunking

Testing and commissioning of Spiral Waste Bin & Bin Lifter System can be conducted immediately after the installation of the system (2 working days for installation)



INSTALLTION OF THE SPIRAL WASTE BIN SYSTEM AT PROJECT SITE

### MAHA MEKAR SDN. BHD.

Sales Office : Suite 111, Block A, 1st Floor, Damansara Intan Business Park, No.1, Jalan SS20/27, 47400 Petaling Jaya, Selangor Darul Ehsan Tel : (+603) 7728 3412 Fax : (+603) 7731 0169 E-Mail : info@mahamekar.com Webpage : www.mahamekar.com