# **Spiral Waste Bin System**

Refuse Storage & Handling Solution

www.mahamekar.com

#### THE SPIRAL WASTE BIN SYSTEM

# **Delivery & Installation of Spiral Waste Bin at Project Site**

Our Spiral Waste Bin & Bin Lifter Systems are fully fabricated and pre-tested in our factory prior to delivery to the project site.

Delivery of Spiral Waste Bin & Bin Lifter System to project site is by lorry and loading and unloading of Spiral Waste Bin & Bin Lifter System is using our own crane or forklift

Prior to Delivery of Spiral Waste Bin & Bin Lifter System to project site, our technicians will check with client's Project / Site Manager to ensure the following:

- Supply of electricity for installation & testing (415V, 3 Phase, 32A Isolator)
- Supply of water via tap points for installation and testing purposes
- Clearing of bin centre from debris and building material
- Access road to the bin centre is clear for delivery lorry and crane
- · Operational roller-shutter to ensure the security of the Spiral Waste Bin after installation











## At the Project Site

### Unloading & Positioning of the Spiral Waste BIn System

Upon unloading at project site, the Spiral Waste Bin & Bin Lifter System will be positioned at the optimal location in the refuse centre using rollers and manual labour.





### Installation of the Spiral Waste Bln System

The Spiral Waste Bin & Bin Lifter System will be securely bolted to the floor at the designated position. Each leg of the Spiral Waste Bin System is bolted down with a 6" rawplug and the Bin Lifter System is bolted down with 8 nos. of 6" rawplug.



Testing and commissioning of Spiral Waste Bin & Bin Lifter System can be conducted immediately after the installation of the system (2 working days for installation)







